

Central Public Works DepartmentSTATE: A & N Islands.ESTIMATE NO.:DIVISION:BRANCH: RR

Note:- The entries against each item below should be made accordance with the classification prescribed in Appendix No.4, C.P.W.D. Code.

Name of Work:

Construction of New Nicebari Guest House at South point Port Blair.

Fund:

Major Head

Minor Head

Detailed Head

DEPOSIT WORK

Estimate framed by..MR. S. Venkateshram, Surveyor of works, Consn.
of the probable cost Circle No. I, ARND.....

Rs. 54,35,000/- (WO) + Rs. 6,52,200/- (DC @ 12.00%)

REPOR E P O R THistory:-

This preliminary estimate amounting to Rs. 54,35,000/- (WO) + Rs. 6,52,200/- (DC @ 12.00%) has been framed to cover the probable cost of the above named work for according A/A and E/S from the competent authority.

Design and scope :- This estimate is prepared based on the ~~architectural~~ ^{Arch.} drawing No. AN/A/²⁵⁷². The building will be based double storeyed RCC framed structure with G.C.H.B walling, C.C flooring, ACC/GCI sheet roofing over timber trusses. The ~~proposed~~ ^{Prepared} G.Floor will be 1.50 m above the Ground level.

Following provisions have been made in this estimate (i) Construction of Building per portion. ii.) Foundation in poor soil. iii) Resisting earth quake forces. iv) Termites proof treatment. v) Development of land i/a levelling, grading, internal roads and paths on L.S basis vi) C/O ~~resumex~~ a compound wall of 236 m length.