

388
#1

2.31	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth upto 30 cm measured at a height of 1 m above ground level and removal of rubbish upto a distance of 50 m outside the periphery of the area cleared.				
		1500	Sqm	3	4500
2.27	Supplying and filling in plinth with Stone dust under floors including, watering, ramming consolidating and dressing complete.				
		12.58	Cum	2600	32708
4.1	Providing and laying in position cement concrete of specified grade excluding the cost of cantering and shuttering all work up to plinth level.				
4.1.8	1:4:8 (1 Cement: 4 Coarse Sand: 8 graded Stone aggregate 40mm nominal size)				
		12.58	Cum	6900	86802
4.1.2	1:1½:3 (1 Cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size).				
		163.12	Cum	7950	1296804
4.3	Centering and shuttering including strutting, propping etc. and removal of form work for :				
4.3.1	Foundations, footings, bases for columns.				
		26.26	Sqm	190	4989.40
4.3.2	Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses plinth and string courses fillets etc.				
		304.050	Sqm		57769.50
13.1	12 mm cement plaster of mix :				