

284
17

13.1.1	1:4 (1 cement : 4 fine sand)				
		306.110	Sqm	230	70405.30
18.12	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. External work :				
18.12.3	25 mm dia. nominal bore (Heavy duty)	50.000	Mtr	270	13500
18.12.4	32 mm dia. nominal bore (Heavy duty)	50.000	Mtr	375	18750
18.12.5	40 mm dia. nominal bore (Heavy duty)	70.000	Mtr	400	28000
18.12.6	50 mm dia. nominal bore (Heavy duty)	30.000	Mtr	500	15000
18.12.7	65 mm dia. nominal bore (Heavy duty)	50.000	Mtr	600	30000
18.12.8	80 mm dia. nominal bore (Heavy duty)	50.000	Mtr	800	40000
18.17	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end)				
18.17.1	25 mm nominal bore (Heavy duty)	2.000	Each	650	1300
18.17.2	32 mm nominal bore. (Heavy duty)	2.000	Each	950	1900
18.17.3	40 mm nominal bore (Heavy duty)	2.000	Each	1200	2400
18.17.4	50 mm nominal bore (Heavy duty)	2.000	Each	1700	3400
18.17.5	65 mm nominal bore (Heavy duty)	2.000	Each	3000	6000
18.17.6	80 mm nominal bore (Heavy duty)	2.000	Each	4300	8600
NSR	Transportation of all building materials, tools and plants for use in construction work from South Andaman Division Wimberlygunj Headquarter to construction site at potatang Chadda No-III near about 01 Km in the forest through old approach.				
	Lumpsum	1	LS		
Total Say Rs.					1877248.7 1877249.00

(Rupees Eighteen Lakhs Seventy Seven Thousand Two Hundred Forty Nine Only)